



ADDENDUM NO. 2

to

**SPECIFICATIONS, CONTRACT DOCUMENTS
AND DRAWINGS**

for

**LAS VEGAS SOLID WASTE FACILITY
DRAINAGE IMPROVEMENTS PROJECT**

Bid Package
Published March 14, 2022

Owner:


City of Las Vegas, NM
1700 Grand Avenue
Las Vegas, NM 87701

Engineer of Record:

Souder, Miller & Associates
5454 Venice Ave NE, Suite D
Albuquerque, NM 87113
505.299.0942

This Addendum constitutes clarifications, changes, additions, modifications and/or deletions to the Contract Documents. All provisions of the Contract Documents not affected by this Addendum shall remain in full force. This Addendum is hereby made a part of the Contract Documents to the same extent as those provisions contained in the original Contract Documents and previous Addenda, if any. Receipt of this Addendum shall be acknowledged on the Bid Form.

Raymond J. Smith, P.E.



4/13/22

Date

TO ALL HOLDERS OF CONTRACT DOCUMENTS FOR:

**LAS VEGAS SOLID WASTE FACILITY
DRAINAGE IMPROVEMENTS PROJECT**

ADDENDUM NO. 2

April 13, 2022

This Addendum shall be incorporated into the Contract Documents for the above referenced project.

Item No. 1 – Gross Receipt Tax

The gross receipt tax is the current rate for the City of Las Vegas, which is 8.3958%.

Item No. 2 – Soils/Material Testing

Soils/material testing will be incidental to the project.

Item No. 3 – Clarification to Tack Coat Quantities

The quantity for the item 336.13—Tack Coat on the bid form is revised to reflect the quantity provided on the plans—16,561 square yards. An updated bid form is attached.

BID FORM

Las Vegas Solid Waste Facility - Drainage Improvements Project

ARTICLE 1 – BASIS OF BID

1.01 Bidder will complete the Work in accordance with the Contract Documents for the following price(s):

Note: Gross receipts tax not included.

BID LOT 1					
ITEM NO.	ITEM DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	TOTAL PRICE
4.01	CONSTRUCTION STAKING, COMPLETE	L.S.	1		
6.05	MOBILIZATION, COMPLETE	L.S.	1		
201.01	SITE CLEARING AND GRUBBING, COMPLETE	ACRE	8.1		
201.06	EROSION CONTROL, INCL. ALL LABOR, EQUIP & MATERIALS, CIP	L.S.	1		
204.01	FILL CONSTRUCTION, INCL EXCAVATION, PLACEMENT & COMPACTION OF UNCLASSIFIED MATERIAL, CIP	CU.YD.	195		
301.02	SUBGRADE PREP, 12" AT 95% COMPACTION, CIP	SQ.YD.	16561		
302.01	AGGREGATE BASE COURSE, CRUSHED, 6" AT 95% COMPACTION CIP	SQ.YD.	16561		
343.01	EXISTING PAVEMENT, ASPHALT CONCRETE, REMOVE & DISPOSE, SAWCUT NOT REQUIRED, ANY THICKNESS, INCLUDING HAUL, COMPLETE.	SY	16561		
401.01	GUARDRAIL WITH POSTS, METAL BEAM, EXCEPT END ANCHORS, CIP	LF	287.5		
401.02	GUARDRAIL END ANCHOR, CIP	EA	2		
603.03	PLAIN RIPRAP, CIP	CU.YD.	348.3		
701.1	TRENCHING BACKFILL AND COMPACTION FOR 18" TO 36" SEWER PIPE, UP TO 8' IN DEPTH, PIPE NOT INCLUDED, COMPLETE.	LF	175		
910.103	DRAINLINE REMOVAL, 10" TO 18", EXCLUDING TRENCHING, COMPLETE	LF	240		
910.OX	18" STORM PIPE END SECTION, CIP	EACH	4		
912.01	HIGH PERFORMANCE STORM PIPE, FURNISH AND PLACE IN OPEN TRENCH, CIP	LF	175		
1011.01	SEEDING, CLASS A, NATIVE, CIP	ACRE	8.1		

SUBTOTAL OF BID LOT 1: \$ _____

NMGRT: \$ _____

TOTAL OF BID LOT 1 \$ _____

BID LOT 2					
ITEM NO.	ITEM DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	TOTAL PRICE
336.022	ASPHALT CONCRETE, 2 INCH THICK SUPERPAVE SP-IV	SQ.YD.	33122		
336.12	TACK COAT, CATIONIC EMULSIFIED ASPHALT, CIP	SY	16561		
440.001	REFLECTORIZED PAINTED MARKINGS, 4" WIDTH, CIP	LF	1800		
440.01	REFLECTORIZED PAINTED MARKING, HANDICAP SYMBOL	EACH	5		

SUBTOTAL OF BID LOT 2: \$ _____

NMGRT: \$ _____

TOTAL OF BID LOT 2: \$ _____

TOTAL IN WORDS: _____

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided in the Contract Documents.